



Student, Belgrade Plaza Student - Electrical Labour

Type	Number Available	1st Fix	Expected Hours (Each)	2nd Fix	Expected Hours (Each)	Final Fix	Expected Hours (Each)	Notes
Distribution								
Apartment Sub-Main	142	£ 15.00	0.75					Sub main installed ,clearly labelled, dressed and ready to gland both ends
Communal Distribution Board (inc sub mains)	16	£ 20.00	1	£ 280.00	14	£ -		Complete distribution board installed - circuit identification marked on a chart for all circuits including supply cable
Main Panel Board	1					£ 480.00	24	Complete distribution board installed - circuit identification marked on a chart for all circuits
Busbar	1					£ 800.00	40	Bus bar and brackets fitted along with the tap off box
Lift Supplies	2					£ 80.00	4	Inc. all cable terminations
Firefighting Distribution Board	1					£ 160.00	8	Inc. all cable terminations
Fire Alarm Supply	1					£ 40.00	2	Inc. all cable terminations
Disabled Refuge Supply	1					£ 40.00	2	Inc. all cable terminations
Water Boost Set Supply	1					£ 80.00	4	Inc. all cable terminations
Containment								
Trapeze	960	£ 5.00	0.25					Containment bracketry
Tray/Basket/Trunking	480	£ 12.00	0.6					Rate includes for 3 x tray/baskets to be installed at the same time
Lighting								
Communal Light Point	800	£ 10.00	0.5	£ 10.00	0.5	£ -		First fix - cables installed , dressed and marked £7.00 per point holes drilled £3.00 per point once boarded and not plastered cable to be brought through - 2nd Fix complete installation off light fitting 5% retention until tested
Power								
Communal Power Point	300	£ 10.00	0.5	£ 10.00	0.5	£ -		First Fix-Cables installed neatly in metal back box and marked - 2nd fix terminated 5% retention until tested
Accomodation								
Studio	79	£ 250.00	12.5	£ 200.00	10	£ 50.00	2.5	First Fix- Complete installation including all metal boxing and banding straps, cables marked - lighting points to be drilled out as part of first fix value - 2nd Fix complete installation including distribution labelling, heater fitted and kitchen splashback 5% retention until tested
6-Bed Cluster	51	£ 610.00	30.5	£ 640.00	32	£ 100.00	5	First Fix- Complete installation including all metal boxing and banding straps, cables marked - lighting points to be drilled out as part of first fix value - 2nd Fix complete installation including distribution labelling, heater fitted and kitchen splashback 5% retention until tested